

"On a Mission to Incident and Injury Free"

LONE STAR

Pipelay / Bury Barge



DIMENSIONS

Length	313 ft
Depth	19 ft
Width	90 ft
Normal operating draft	12 ft
Berths	165
Helideck	40 ft x 35 ft
Class	ABS A-1
Registry	Vanuatu

MECHANICAL EQUIPMENT

Main generators	2 x 1,200 kW
Emergency generator	1 x 150 kW
Air compressors	2 x 900 cfm @ 150 psi
Water maker	20,000 GPD

CRANES

Bow	2 x Manitowoc 4000/3900
Type	Crawler
Capacity	88/73 T
Boom length	120 ft
Stern	Manitowoc 3900
Type	Pedestal
Capacity	56 T
Boom length	120 ft

CAPACITIES

Water	138,000 USG
Fuel	224,000 USG

PIPE LAYING EQUIPMENT

Welding stations	4 (max)
Pipe tensioner	2 x 88 Kips each
Capacity	176 Kips
Abandon/rec. winch	
Capacity	88 T average drum
Wire size	up to 2 in
Wire length	up to 5,000 ft
Pipe diameter	36 in (max)
Davits	4
Capacity	50 T each

PIPE BURY EQUIPMENT

Portable jetting equipment available

MOORING SYSTEM

8 anchors with 4 Intercon double drum winches with up to 5,000 ft of 2 in (max) cable



Cal Dive International, Inc.
Corporate Office
2500 CityWest Blvd., Suite 2200
Houston, Texas 77042
877-361-2600
www.caldive.com